

<b>AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT</b>		1. CONTRACT ID CODE	PAGE OF PAGES 1 of 1
2. AMENDMENT/MODIFICATION NO. <div style="text-align: center;">12</div>	3. EFFECTIVE DATE <div style="text-align: center;">11-Mar-2002</div>	4. REQUISITION/PURCHASE REQ. NO.	5. PROJECT NO. <i>(If applicable)</i>
6. ISSUED BY US Army Corps of Engineers, Kansas City District 760 Federal Building, 601 East 12th Street Kansas City, Missouri 64106-2896		7. ADMINISTERED BY <i>(If other than item 6)</i>	
8. NAME AND ADDRESS OF CONTRACTOR <i>(No., street, county, State and ZIP Code)</i>		(X) 9a. AMENDMENT OF SOLICITATION NO. X DACW41-02-B-0001 9b. DATED <i>(SEE ITEM 11)</i> 12/22/2001 10a. MODIFICATION OF CONTRACT/ORDER NO. 10b. DATED <i>(SEE ITEM 13)</i>	
CODE                      FACILITY CODE		11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS	
<input checked="" type="checkbox"/> The above number solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers <input type="checkbox"/> is extended, <input checked="" type="checkbox"/> is not extended. Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods: (a) By completing Items 8 and 15, and returning _____ copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegraph which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.			
12. ACCOUNTING AND APPROPRIATION DATA <i>(If required)</i>			

13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS, IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.	
(X)	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: <i>(Specify authority)</i> THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.
	B. THE ABOVE NUMBER CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES <i>(such as changes in paying office, appropriation date, etc.)</i> SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF:
	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:
	D. OTHER <i>(Specify type of modification and authority)</i>

**E. IMPORTANT:** Contractor ☐ is not, ☐ is required to sign this document and return \_\_\_\_\_ copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION <i>(Organized by UCF section headings, including solicitation/contract subject matter where feasible.)</i>	
Missouri River Levee System, Levee Unit L-385 Phase I - Quindaro Levees and Stop Log Gap, Phase II - Quindaro-Riverside Levees and Structures  The Solicitation is amended in accordance with the attached pages.	

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER <i>(Type or print)</i>		16A. NAME AND TITLE OF CONTRACTING OFFICER <i>(Type or print)</i>	
15B. CONTRACTOR/OFFEROR		16B. UNITED STATES OF AMERICA	
15C. DATE SIGNED		16C. DATE SIGNED	
_____ <i>(Signature of person authorized to sign)</i>		BY _____ <i>(Signature of Contracting Officer)</i>	

Project: Missouri River Levee System, Quindaro Levee and Stoplog Gap,  
(Levee Unit L-385) Riverside, Missouri

### BIDDING SCHEDULE

#### OPTION SCHEDULE PHASE II

ITEM NO.	DESCRIPTION	EST QTY	UNIT	UNIT PRICE	SUBTOTAL	AMT
	GW#11 Relief Wells 1 thru 4		LS		\$_____	
	Sewer System #1 - Design		LS		\$_____	
	Sewer System #1 - Construction		LS		\$ 775,000	
	Drainage System #2		LS		\$_____	
	Drainage System #3		LS		\$_____	
	Drainage System #4		LS		\$_____	
	Drainage System #5		LS		\$_____	
	Drainage System #6A		LS		\$_____	
	Drainage System #6B		LS		\$_____	
	Drainage System at 9B		LS		\$_____	
	Interior Detention Basin South Red-X		LS		\$_____	
	Red-X Ditch		LS		\$_____	
	Drainage System @ Prologis		LS		\$_____	
	Drainage System @ Prologis, Tract 187					
	Relief Wells 7&8 @ Prologis		LS		\$_____	
	Gabions @ Floodwall		LS		\$_____	
	Modular Block Wall at Kitterman		LS		\$_____	
0109a	Government Field Office (OPTION 1)	36	MONTHS	\$_____		\$_____
0109b	Anti-Graffiti Sealer (OPTION 2)	54,300	SF	\$_____		\$_____

**TOTAL BASE AND OPTION SCHEDULE PHASE II \$\_\_\_\_\_**

Project: Missouri River Levee System, Quindaro Levee and Stoplog Gap,  
(Levee Unit L-385), Riverside, Missouri

**BIDDING SCHEDULE (PHASE II BID NOTES)**

- Relief Wells 7&8 @ ProLogis - The work includes all costs associated with mob/demob to the site, drilling for wells, provision and installation of well casing, screens, plugs, centralizers, filter pack, grout, outflow pipe, flap gate, pvc pipe, and metals for lid; sterilization; pump test; soil tests. Also included is the cost for the construction of the vaults.
- Gabions @ Floodwall – This item includes all cost associated with furnishing, hauling, handling, placing, and maintaining the riprap and cages until final acceptance by the government for the gabion protection at the floodwall.
- Modular Block Wall at Kitterman – Work includes all cost associated with the excavation; forming and placement of leveling pad; furnishing, handling and placement of modular block, drainage pipe, and geogrid; and backfilling/compaction of granular backfill and topsoil. The contractor shall also be responsible for all costs associated with the design of the modular block wall.

0109a: Government Field Office – Bidder is directed to Section 01500 TEMPORARY CONSTRUCTION FACILITIES.

0109b: Anti-Graffiti Sealer -- This item includes all costs associated with the furnishing/application of anti-graffiti sealer to the walls of: Q0 North/South transition; M21/M22, and the Closure Monolith; Q3a – M28/M29, and Closure Monolith; R1a – I-wall, M25/M26, and Closure Monolith; R2 – I-wall, Storage Monolith, Closure Monolith (S), Closure Monolith (N), Floodwall Monolith (1), Floodwall Monolith (2), Floodwall Monolith (3), and M27; Riverside Floodwall – both sides.

DACW41-02-B-0001-0012

Project: Missouri River Levee System, Quindaro Levee and Stoplog Gap,  
(Levee Unit L-385), Riverside, Missouri

**BIDDING SCHEDULE (PHASE I + PHASE II BID NOTES)**

- Relief Wells 7&8 @ ProLogis - The work includes all costs associated with mob/demob to the site, drilling for wells, provision and installation of well casing, screens, plugs, centralizers, filter pack, grout, outflow pipe, flap gate, pvc pipe, and metals for lid; sterilization; pump test; soil tests. Also included is the cost for the construction of the vaults.
- Gabions @ Floodwall – This item includes all cost associated with furnishing, hauling, handling, placing, and maintaining the riprap and cages until final acceptance by the government for the gabion protection at the floodwall.
- Modular Block Wall at Kitterman – Work includes all cost associated with the excavation; forming and placement of leveling pad; furnishing, handling and placement of modular block, drainage pipe, and geogrid; and backfilling/compaction of granular backfill and topsoil. The contractor shall also be responsible for all costs associated with the design of the modular block wall.

0200: Government Field Office – Bidder is directed to Section 01500 TEMPORARY CONSTRUCTION FACILITIES.

0201: Anti-Graffiti Sealer – This item includes all costs associated with the furnishing/application of anti-graffiti sealer to the walls of: Q0 North/South transition; M21/M22, and the Closure Monolith; Q3a – M28/M29, and Closure Monolith; R1a – I-wall, M25/M26, and Closure Monolith; R2 – I-wall, Storage Monolith, Closure Monolith (S), Closure Monolith (N), Floodwall Monolith (1), Floodwall Monolith (2), Floodwall Monolith (3), and M27; Riverside Floodwall – both sides.